CREATIVE DESIGN BOLD FACE COPING

8" WIDE SPLICE PLATE WITH
DUAL NON-CURING SEALANT
STRIPS AT EACH JOINT

COPING COVER
12'-0" LENGTHS

12" WIDE GALV. ANCHOR CLIPS
SPACING TO BE DETERMINED BY
MANUFACTURER

$1\frac{3}{8}$"

$\frac{15}{16}$"

INSIDE FACE
MIN. $2\frac{1}{4}$"
MAX 6"

OUTSIDE FACE
MIN. $4\frac{1}{2}$"
MAX 12"

FASTENERS PROVIDED

2"

$\frac{3}{8}$" SPACE PROVIDED
FOR WALL VARIATION

ACTUAL WALL WIDTH
MIN. 5" MAX. 24

-- CONCEALED SPLICE PLATES ARE PROVIDED WITH FACTORY APPLIED NON-CURING SEALANT STRIPS.

-- UNLESS OTHERWISE NOTED, FABRICATION OF MITERS AND ACCESSORIES ARE FURNISHED STANDARD UTILIZING A NON-PENETRATING QUICKLOCK JOINT, THEN FACTORY SEALED WATERTIGHT.

Fabrication will proceed only after receipt of signed print approval.

Print Approval:

Architect and/or contractor shall verify all dimensions, sizes and quantities. All products to be installed in strict accordance with Metal-Era's printed instructions.

Approved by: _____

Date: _____

PLEASE SPECIFY SUBSTRATE:
(IF SUBSTRATE INFORMATION
IS NOT GIVEN, WOOD SUBSTRATE
FASTENERS WILL BE PROVIDED)

☐ WOOD
☐ MASONRY
☐ METAL

-- WELDED MITERS AND ACCESSORIES
CHECK ONE ☐ REQUIRED (SURCHARGE) ☐ NOT APPLICABLE

MATERIAL:

___ 24 GA. GALV.   ___ .050" ALUMINUM
___ 22GA GALV.   ___ .063" ALUMINUM
___ .040" ALUMINUM   ___ OTHER _____
COLOR:_____   FINISH:_____

QUANTITIES:

_____ LINEAL FEET 12'-0" LENGTHS

_____ OUTSIDE MITERS @ 90°

_____ INSIDE MITERS @ 90°

_____ RIGHT ENDCAPS

_____ LEFT ENDCAPS

FOR NON-90° MITERS SEE SEPARATE PRINT APPROVAL

PROJECT:	Corporate Offices, Manufacturing
ARCHITECT:	1600 Airport Road; Waukesha, WI 53188
ROOFING CONTRACTOR:	Phone: 800-558-2162
REPRESENTATIVE/DISTRIBUTOR:	Fax: 800-373-9156
	www.metalera.com

METAL-ERA®
Roof Edge Solutions

DATE: 07/18/23	SHT.#____ OF ____
DRN BY: MLM	
CKD BY: MM	DWG# 11011-28630	E