
## HI-PERF RIDGE VENT

### SLOPED ROOF MEETS VERTICAL WALL, STANDING SEAM VERSION

#### **INSTALLATION INSTRUCTIONS**



CAUTION! INSTALLERS SHALL WEAR PROTECTIVE EYE WEAR TO PREVENT INJURY. DO NOT OVERDRIVE FASTENERS, AS STRIPPING CAN OCCUR AT HIGH DRIVER TORQUE. RECOMMENDED DRIVING TOOL: 600 - 800 rpm ELECTRIC DRILL EQUIPPED WITH DEPTH-SENSING NOSE-PIECE TO PREVENT DRIVING AND STRIPOUT. DO NOT USE IMPACT TYPE TOOL.

IMPORTANT! BE SURE TO REMOVE PROTECTIVE PLASTIC FILM PRIOR TO INSTALLING EACH COVER SECTION.

NOTE: ALL FASTENERS MUST MEET MINIMUM 240 LB. PULL-OUT FOR SUBSTRATE.



Phone: 800-558-2162 Fax: 800-770-3934 www.metalera.com

DATE: 03/10/16 DRN BY: JJC

SHT.#<u>1</u> OF <u>5</u>


CKD BY: SAK

DWG# 31124-15038

# I-PERF RIDGE VEN


SLOPED ROOF MEETS VERTICAL WALL, STANDING SEAM VERSION

#### INSTALLATION INSTRUCTIONS



#### 1. PREPARE RIDGE

CUT OPENING AT RIDGE "X" DIMENSION. (SEE DETAIL "A".)




#### 3. STANDING SEAM ROOFING

FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR TERMINATING STANDING SEAM AT RIDGE VENT CHANNEL. SEE ABOVE FOR TYPICAL DETAIL.

TO PREVENT MOISTURE ENTRY UNDER THE "Z", APPLY A GENEROUS BEAD OF NON-CURING SEALANT TO BOTTOM OF FLANGE. FASTEN BRACKETS AT ROOF AT 6" O.C. WITH APPROPRIATE FASTENERS USING PRE-PUNCHED SLOTTED HOLES. LAP "Z'S" 1".

NOTE: FOAM/SEALANT SHOULD BE PLACED BETWEEN THE "Z" AND VERTICAL WALL OVER THE OSB ON THE LAST 6" AT BOTH ENDS (SEE STEP 1)



FASTEN CONTINUOUS CLEAT TO WALL IN FACE AND TOP FLANGE 12" O.C. AS SHOWN USING APPROPRIATE FASTENERS FOR SUBSTRATE.



Phone: 800-558-2162 Fax: 800-770-3934 www.metalera.com


DATE: 03/10/16 SHT.#\_2 OF \_5 DRN BY: JJC

DWG# 31124-15038 CKD BY: SAK


# HI-PERF RIDGE VENT

### SLOPED ROOF MEETS VERTICAL WALL, STANDING SEAM VERSION

#### **INSTALLATION INSTRUCTIONS**



PLACE SCREEN CENTERED OVER "Z" BRACKETS.
TEMPORARILY FASTEN TO "Z" BRACKETS AT EACH END
OF 12'-0" LENGTH TO HOLD IN PLACE.



#### **6. INTERMITTENT SPACERS**

STARTING AT THE END OF THE ROOF WHERE THE ENDCAPS WILL BE PLACED, FASTEN INTERMITTENT SPACERS THRU SCREEN INTO "Z" BRACKET AND CONTINUOUS CLEAT. THE FIRST SPACER SHOULD BE 4" O.C. FROM THE END OF WALL. THE SECOND SPACER IS 8" O.C. FROM THE FIRST SPACER. CONTINUE INSTALLING SPACERS AT 12" O.C. AS SHOWN. USE APPROPRIATE FASTENERS. THE REASON FOR THE SECOND SPACER IS THAT IT IS ADVANTAGEOUS TO HAVE A SPACER AT THE JOINTS. IT IS RECOMMENDED THAT THIS PRACTICE CONTINUES THROUGHOUT THE INSTALLATION. IMPORTANT: THE BENDS ON TOP OF THE SPACER MUST ALL BE FACING AWAY FROM THE END OF THE ROOF.



Phone: 800-558-2162 Fax: 800-770-3934 www.metalera.com

DATE: 03/10/16

DRN BY: JJC


SHT.#<u>3</u> OF <u>5</u>

CKD BY: SAK

DWG# 31124-15038


# HI-PERF RIDGE VENT SLOPED ROOF MEETS VERTICAL WALL, STANDING SEAM VERSION

#### INSTALLATION INSTRUCTIONS



# HI-PERF RIDGE VENT SLOPED ROOF MEETS VERTICAL WALL, STANDING SEAM VERSION

#### INSTALLATION INSTRUCTIONS



APPLY A GENEROUS BEAD OF NON-CURING SEALANT (BY OTHERS) TO EACH SIDE OF JOINT. HOOK COVER PLATE ONTO COVER AT JOINTS AND ROTATE INTO PLACE. POP RIVET INTO COVER PLATE AT ONE SIDE OF THE JOINT (FASTEN SIDE WHICH HAS 90° DRIP ANGLE). THIS WILL PREVENT MIGRATION.



Phone: 800-558-2162 Fax: 800-770-3934 www.metalera.com

DATE: 03/10/16 SHT.#\_5 OF \_5 DRN BY: JJC

CKD BY: SAK

DWG# 31124-15038